PREMIER MEDIA
INTEGRATION

Premier Media Integration, INC
936 Detroit Avenue, Suite N
Concord, CA 94518
Phone: 925.349.9954
CA License #976517

5/9/16

Jefferson School District
1219 Whispering Wind Drive
Tracy, CA 95377
James W. Bridges, Superintendent

RE: Acoustic Analysis and Design

Professional Services: Acoustical Measurement

- Acquire Room Impulse Response (RIR) measurements

Using a Type I measurement microphone with calibrated input to a computer running measurement software. A sound stimulus is input into a test loudspeaker (Dodecahedron + Subwoofer) to acquire the RIR at no less than four locations within the room.

- Data Sets Included:
  - T30: Room Reverberation
  - ETC: Energy Time Curve

- Cost $1,240.00 per school

Professional Services: Acoustical Design & Specifications

- Create 3D room model in Enhanced Acoustical Simulation for Engineers (EASE) software from owner supplied plans.
- Adjust model to best correlation with acoustical measurements
- Input Loudspeakers and analyze RIR data, providing the following data sets:
  - ETC: Energy Time Curve
  - STI: Speech Intelligibility per IEC 60268-16
- Input Acoustical Treatment into room model and analyzer RIR data, providing the following data sets:
  - ETC: Energy Time Curve
  - STI: Speech Intelligibility per IEC 60268-16
- Convolve before and after acoustical treatment RIR data with speech for owner review of results of before and after treatment
- Provide computer generated drawings of room surfaces with acoustical treatment
- Write report summarizing results of analysis and design
- Provide opinion of probable cost (OPC) for installed acoustical treatment package(s)

- Cost $1,760.00 per school

JAM SERVICES, INC.

958 E Airway Blvd
LIVERMORE, CA 94550

Telephone (925) 455-5267
Fax (925) 455-5348

PRICE QUOTATION – JEM052316A REVISED 7/18/16

Wilson Architecture Inc
5/23/16

JAM Services is pleased to provide the following price quotation for the subject project.

QTY (4) Solar R829C Flashing Beacon [Y] 12" w/2" Round Mount (Green Signal Housing)

UNIT PRICE: $2,650.00 TOTAL PRICE: $10,600.00

QTY (1) Calendar Programming Kit

UNIT PRICE: $435.00 TOTAL PRICE: $435.00

RECEIVED JUL 18 2016

Steel/Iron Pole and Base Assembly:
QTY (4) PB-5200-15-GLV Galvanized Steel Pole 15'

QTY (4) PB-5511-GLV Galvanized Iron Base

QTY (4) PB-5306-GLV Anchor Bolt Kit

UNIT PRICE: $625.00/assembly TOTAL PRICE: $2,500.00

Aluminum Pole and Base Assembly:
QTY (1) PB-5100-15-PNC Aluminum Pole 15'

QTY (1) PB-5334-PNC Aluminum Base

QTY (1) PB-5306-GLV Anchor Bolt Kit

UNIT PRICE: $450.00/assembly TOTAL PRICE: $1,800.00

EITHER/OR NOT BOTH

Prices include delivery, but are net of applicable sales tax. If I can be of further assistance, please contact me at 925-455-5267.

Thank you - Jason Momaney

Req 17-00311

PROPOSAL

P.W.F.

Precision Wall Finishes

PO Box 1005
Salida, CA 95368
Lic #927917

Gary J. McAndrews
gjmlp@sbcglobal.net
Gary W. McAndrews
gmcandrews6@sbcglobal.net

Phone: 209-522-3040
Fax: 209-522-3050
Cell: 209-606-4511

Proposal Submitted To: Jefferson School District	Phone: (209) 83406109	
Street: 1219 Whispering Wind Drive	Job Name: Lighting project	
City: Tracy State: CA Zip Code: 95377	Job Location: 7500 W. Linn Rd., Tracy, CA	
Attention: **Sam Hagler**	Date of Plans :	Date: 09/20/2016

We hereby submit specification and estimates for the following:

To remove the existing posts and signs in four (4) locations and re-install new posts, set in concrete, install signs, and install flashing beacons and solar system to power the beacons at the four (4) locations as per the architectural drawings by Wilson Architecture and as shown on page A-O of said plans.

All materials to be supplied by the school district except for the cement at the pole locations.

We will provide all necessary labor and will off-haul and dispose of debris.

Our DIR # is 1000014699

This job is not figured at pre-vailing wage rates as it is not required due to it being repairs.

We propose hereby to furnish material and labor— complete in accordance with the above specifications, for the sum of:
($4,236.00) Four Thousand Two Hundred and Thirty-Six Dollars and no/100
Payments to be made as follows: 100% Payment upon completion
All labor and material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents, or delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered under Workmen's Compensation Insurance. Smooth finishes are subject to excessive cracking and discoloration, which is beyond our control. No warranty to be honored with smooth finish stucco.
Authorized Signature: _____ Date: (09/20/2016)
Note: this proposal may be withdrawn by us if not accepted within (30) days.

Acceptance of proposal — The above prices, specifications, and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above:
Date: 9/20/16 Signature: _____ Signature: _____

21-7711.0-0000.8500.5800.110.0000 $ 4,236.00